



POOLMASTER
BUILT TO LAST



2024 PRODUCT CATALOG



PASSION | DEDICATION | INTEGRITY

POOLMASTER



OUR HISTORY

Established in 2021, as a distribution company that focuses on wholesale and retail of swimming pool equipment, tools, and cleaning materials, offering the best option available in the market that will suit your needs and satisfaction.



OUR VISION

We are dedicated to providing the best quality materials and service that our customer needs for their swimming pool. We strive to build long term relationships with our clients with the dedication, passion, and integrity that we put in with our service.



OUR MISSION

To be the leading swimming pool supplier and builder in the country, renowned for world-class design and construction, that is dedicated to exceptional customer satisfaction. To always improve and innovate our ways to provide the best option for our customers



 **02 8-557-1585**
 **+639158881660**
 **THEOFFICIALPOOLMASTER88@GMAIL.COM**

ABOUT US

Our founders noticed a shift in the way people shop, buy and inquired for their swimming pool needs. From this shift, a company was born: Poolmaster. Rooted in the concept of "Built to Last," Poolmaster is founded on the belief that individuals should relish their swimming pool experiences, creating enduring memories in a leisurely and lasting manner.

WHY CHOOSE US?

Our passion lies in crafting swimming pools that are not only designed for today's moments but also Built to Last for generations.



Service Hub

Our expert customer service makes it easy to connect with customers and help them with their inquiries.



Sales Hub

Our Sales and Product lines include full suite of world -class brands for your pool needs.




Operation Hub

Our operations are streamlined, your purchases delivered right at your doorstep.



TABLE OF CONTENTS

Building, repairing, and maintaining a swimming pool shouldn't be a challenge. At Poolmaster, we're dedicated to making it a hassle-free experience for you.



Pool Consumables

Our top-notch consumables are designed for durability and effectiveness, carefully crafted to redefine pool care, ensuring your swimming pool remains crystal-clear and inviting.

01

Pool Equipment

We offer a full range of industry-leading equipment designed to help every residential and commercial pool perform at its absolute best.

02

Pool Accessories

Our high quality of materials and the rigorous controls of production processes guarantee a long life for our equipment.

03

Client Portfolio

Our portfolio also includes maintenance, repair services and swimming pool building of our clients - Testament to our passion for creating beautiful and functional pools that are 'Built to Last.'

04



02 8-557-1585

theofficialpoolmaster88@gmail.com

PRISTINE & CRYSTAL CLEAR SWIMMING POOL

**EASY TO USE FOR
POOL MAINTENANCE**



QUALITY GUARANTEED



FUJICHLON
(CALCIUM HYPOCHLORITE 70%)
Fuji Kasei Co., Ltd.

- Made in Japan
- 45 kgs/ drum

SHOP NOW



STAR -CHLON
(CALCIUM HYPOCHLORITE 70%)
Nankai Chemical

- Made in Japan
- 45 kgs/ drum
- Premium Chlorine

SHOP NOW



NICLON 7000
(CALCIUM HYPOCHLORITE 70%)
TOSOH Chemicals

- Japan Quality
- 45 kgs/ drum

SHOP NOW



SUPER -CHLOR
(CALCIUM HYPOCHLORITE 70%)
Qingdao Pool Chemical

- Made in China
- 40 kgs/ drum

SHOP NOW



NEO-CHLOR
(TRICHLOROISOCYANURIC ACID TCCA/ TICA 90%)
Shikoku Chemicals

- Made in Japan
- 50 kgs/ drum
- Granular or Tablet

SHOP NOW



AQUACARE SDIC 60%
SODIUM DICHLOROISOCYANURIC ACID (SDIC) 60%
Shikoku Chemicals

- Made in Japan
- 4 kgs/ pail

SHOP NOW



PRISTINE & CRYSTAL CLEAR SWIMMING POOL

**EASY TO USE FOR
POOL MAINTENANCE**



QUALITY GUARANTEED



SILICA SAND
SAND FILTER FILTRATION MEDIA
Silica Sand

- Made in Malaysia
- Grain Size #20
- 22.7 kgs/ bag

SHOP NOW



SILICA SAND
SAND FILTER FILTRATION MEDIA
Silica Sand

- Made in USA
- Grain Size #20
- 22.7 kgs/ bag

SHOP NOW



HYDROMAX GLASS MEDIA
SAND FILTER FILTRATION MEDIA

- Made in China
- 0.5-1.55 mm (Fine)
- 1-3 mm (Coarse)
- 25 kgs/ bag

SHOP NOW



POOLMATE
CONCENTRATE ALGAECIDE 60%

- Made in USA
- 950 mL / bottle
- Reduces Chlorine use

SHOP NOW



GLB ALGIMYCIN 600
CONCENTRATE ALGAECIDE 60%

- Made in USA
- 946 mL / bottle
- Reduces Chlorine use

SHOP NOW



DICALITE D.E. POWDER
D.E. FILTER FILTRATION MEDIA
Diatomaceous Earth

- Made in USA
- 22.7 kgs/ bag

SHOP NOW



PRISTINE & CRYSTAL CLEAR SWIMMING POOL

**EASY TO USE FOR
POOL MAINTENANCE**



QUALITY GUARANTEED



POOL CARE DRY ACID

SODIUM BISULPHATE

Fortuna Kimya - Turkey

- Made in Turkey
- 5 kgs/ pail

SHOP NOW



AQUACARE DRY ACID

SODIUM BISULPHATE

Jones -Hamilton Co., USA

- Made in USA
- 5 kgs/ pail

SHOP NOW



NATRIUMBISULFAT

SODIUM BISULPHATE

Dry Acid / PH Reducer

- Made in Turkey
- 25 kgs/ bag

SHOP NOW



COPPER SULPHATE

COPPER SULPHATE - PENTAHYDRATE

Algaecide

- Made in Taiwan
- 25 kgs/ bag

SHOP NOW



POTASSIUM ALUM

POTASSIUM ALUMINUM SULFATE

Pool clarifier / Flocculant

- Made in China
- 25 kgs/ bag

SHOP NOW



THALASSO SALT

DISINFECTING AGENT

Can be used with Salt Chlorinator

- 20 kgs/ bag

SHOP NOW



PREMIUM POOL PUMPS & FILTERS



For nearly 100 years, Hayward has built industry-leading equipment, filters, and pumps. Today Hayward are at the forefront of innovation for pool and outdoor living technology and internet-connected homes.



QUALITY GUARANTEED




HAYWARD MAXFLO XL SERIES

For entry-level new construction and aftermarket applications, MaxFlo XL™ is the medium head pool pump that provides advanced hydraulics and the latest conveniences while maintaining the economy & performance of the proven MaxFlo.



Model	Motor HP	TDH FT.	Flowrate GPM	Volts
SP2305X7	0.75	30	55	230
SP2307X10	1.0	30	70	230
SP2310X15	1.5	30	81	230
SP2315X20	2.0	30	103	230

MAXFLO XL MEDIUM HEAD PUMPS




HAYWARD SUPER II SERIES PUMP

These efficient large capacity pumps are built to last and engineered to perform even under the most demanding conditions. Performance features include full flow hydraulics that allow greater flow.



Model	Motor HP	TDH FT.	Flowrate GPM	Volts
SP3015X20AZ	2.0	40	112	230
SP3020X25AZ	2.5	40	132	230
SP3025X30AZIMG	3.0	40	157	230

SUPER II Flow vs. Total Head



HAYWARD


TRISTAR XE PUMP

These ultra efficient large capacity pumps are built to last and engineered to perform even under the most demanding conditions.

Performance features include full flow hydraulics that allow greater flow.




TRISTAR XE MAX SPEED PERFORMANCE COMPARISON



HAYWARD

SWIMPRO PUMP

SwimPro pumps is ideal for small pool application. It is small in size but not small on features and performance. The self priming pump features a silent running totally enclosed fan cooled moto as well as union connections and an easy to use cam-lock.



Model	Motor HP	TDH FT.	Flowrate GPM	Volts
SP3207X10XE	1.0	40	78	230
SP3210X15XE	1.5	40	110	230
SP3215X20XE	2.0	40	140	230

Model	Motor HP	TDH FT.	Flowrate GPM	Volts
SWP1205	0.5	30	47	230
SWP1207	0.75	30	57	230
SWP1210	1.0	30	66	230
SWP1215	1.5	30	75	230



From our residential and commercial water solutions, to industrial water management and everything in between, Pentair is focused on smart, sustainable water solutions that help our planet and people thrive.


WHISPERFLO

HIGH PERFORMANCE

Pentair is proud to announce updates to the line of WhisperFlo High Performance Pumps. We've added the first and only single-speed pump models to use NEMA Premium® Efficient motors for pool applications.*



Pump Performance Curves



Product	Model	Motor HP	TDH (Ft.)	Flow Rate (GPM)	Voltage (Volts)	Full Load (Amps)	Curve Key
011511	WFE-2	1/2	18	90	230	4.4	E
011512	WFE-3	3/4	18	98	230	6.4	F
011513	WFE-4	1	22	118	230	7.4	G
011514	WFE-6	1-1/2	28	135	230	8.8	H
011515	WFE-8	2	31	148	230	10.2	I
011516	WFE-12	3	38	170	230	13.6	J


Emaux's production facility is ISO9001 certified, and the most stringent international standards have been met for individual products. The rapid advance in technology and the complexity of machines and devices have made quality assurance (QA) more critical and challenging. Emaux's quality policy is to ensure safe and trouble-free products are supplied to the market.

EMAUX SPH SERIES

Strong, reliable and performing pump to suit the professionals needs on new installations and retrofit. And we listen our customers, the result is Super-Power pump.



SS 050		Emaux super pump 0.50hp	15	40FT	220V/60HZ
SPH075	88029704	Super Power PUMP Series 0.75hp	20	40FT	220V/60HZ
SPH100	88029705	Super Power PUMP Series 1.00hp	55	40FT	220V/60HZ
SPH150	88029707	Super Power PUMP Series 1.50hp	73	40FT	220V/60HZ
SPH200	88029708	Super Power PUMP Series 2.00hp	88	40FT	220V/60HZ
SPH300	880297091	Super Power PUMP Series 3.00hp	100	40FT	220V/60HZ




EMAUX SC SERIES

The SC pump is quiet running and energy efficient. 1.5-inch suction and discharge port with a transparent lid. It operates at a low decibel and energy consumption which requires minimal maintenance.



SC 100	SC 100 POOL PUMP	55	30FT	220V/60HZ
SC150	SC 150 POOL PUMP	60	30FT	220V/60HZ




EMAUX SB SERIES

The SB Series pump delivers high flow and energy efficiency ultra performance. 2-inch suction and discharge port with a transparent lid. Ring lock seal design to eliminate suction leaks and to maximize suction efficiency.



SB10	SB10 2" 1.0HP POOL PUMP	55	30FT	220V/60HZ
SB15	SB15 2" 1.5HP POOL PUMP	88	30FT	220V/60HZ
SB20	SB20 2" 2.0HP POOL PUMP	110	30FT	220V/60HZ
SB30	SB30 2" 3.0HP POOL PUMP	128	30FT	220V/60HZ



HAYWARD PRO -GRID D.E. FILTER

Pro Grid filter tanks are constructed of a durable glass reinforced copolymer for the ultimate in strength, durability and long life.

Model	Filter Area Sq. Ft.	Flow Rate GPM	Tank Dia. Inches	D.E. Powder Required KGS
DE3620	36	72	24"	2.0
DE4820	48	96	24"	2.7
DE6020	60	120	24"	3.4
DE7220	72	144	24"	4.0
DEX2400PAK2CS	Coupling Kit			



HAYWARD PRO -SERIES SAND FILTER

Pro Series sand filters feature unitized construction of corrosion-proof polymeric material and self cleaning 360 degree slotted laterals.

A versatile seven position control valve offers both easy operational and maximum efficiency.

Model	Filter Area Sq. Ft.	Flow Rate GPM	Tank Dia. Inches	Filter Media Required KG
S244T	3.14	62	24"	136
S270T	3.70	74	27"	159
S310T2	4.91	98	31"	227
S360T2	7.06	141	36"	318



HAYWARD STAR CLEAR PLUS CARTRIDGE FILTER

Star Clear Plus filter is high performance pool filter for residential applications. Manufactured from durable, corrosion proof materials and utilize a reusable cartridge element.

Model	Filter Area Sq. Ft.	Flow Rate Residential GPM
C500	50	50
C751	75	75
C900	90	90
C12002	120	120





PENTAIR FNS PLUS D.E. FILTER

FNS Plus Filters are designed with curved grids to maximize filtration area. More filter area means better performance and longer periods between cleanings.

Product No	Model	Filter Area (sq.ft.)	Flow rate (GPM)	Turn over Cap (gal)	Tank Dia. (in.)	Wt. (Lbs.)	D.E. Req'd (Lbs.)
180006	FNSP 24	24	48	23,040	21.5	60	2.4
180007	FNSP 36	36	72	34,560	21.5	70	3.6
180008	FNSP 48	48	96	46,080	21.5	80	4.8
180009	FNSP 60	60	120	57,600	21.5	90	6.0
263064	Valve Pushpull 7.5" cntr PVC Almd						
271096	Adapter Kit – FNS Filter						
261152	Hi-Flow Valve 2" Pre-plumbed						

Note: Price of valve and adapter kit not included




PENTAIR EASY CLEAN D.E. FILTER

The EasyClean D.E. Inground Filter makes it even easier to enjoy the added water clarity that only D.E. media can deliver. This simple, trouble-free and highly effective filter features a fiberglass-reinforced, chemical-resistant, polypropylene tank with no-tool servicing for easier cleaning.

Model Number	Filter Area Sq. Ft.	Vertical Clearance*	Filter Diameter	D.E. Required (lbs.)	Flow Rate GPM	Turnover Capacity (Gallons)		
						8 hrs.	10 hrs.	12 hrs.
EC60	15	39 in	15.5 in	1.3	60	28,000	36,000	43,000
EC90	30	76 in	15.5 in	2.4	90	43,200	54,000	64,800

*Required clearance to remove filter elements **Maximum flow rate





EMAUX CF SERIES CARTRIDGE FILTER

comes with a UV resistant tank and a heavy duty ring-lock lid which allows easy cleaning and replacement of the cartridge element. A screw type air bleed valve releases trapped air inside the filter tank. The high quality oil-filled pressure gauge provides an easy overview of the operating pressure.


CF50	88060102	CF50 50ft2 Cartridge Filter with 1.5" union sets	50	ELEMENT	1.5"
CF75	88060103	CF75 50ft2 Cartridge Filter with 1.5" union sets	75	ELEMENT	1.5"
CF100	88060104	CF100 100ft2 Cartridge Filter with 2" union sets	101	ELEMENT	2.0"
CF150	88060105	CF150 150ft2 Cartridge Filter with 2" union sets	147	ELEMENT	2.0"
CF200	88060106	CF200 200ft2 Cartridge Filter with 2" union sets	180	ELEMENT	2.0"



EMAUX V SERIES SAND FILTER

are manufactured by automatic bobbin winding technology from long-lasting and non-corrosive fiberglass and resin. The UV resistant composites allow the filter to resist extreme weather conditions for a long working life without corrosion.

V650	88010105	V650 Φ 25" Top Mount Filter, 1.5" valve Vseries Sand Filter	69	145 KG	1.5"
V700	88010107	V700 Φ 28" Top Mount Filter, 1.5" valve Vseries Sand Filter	86	210	1.5"
V800	88010609	V800 Φ 32" Top Mount Filter, 2.0" valve Vseries Sand Filter	110	355	2.0"
V900	88010610	V900 Φ 36" Top Mount Filter, 2.0" valve Vseries Sand Filter	137	470	2.0"
V1000		V1000 Φ 36" Top Mount Filter, 2.0" valve Vseries Sand Filter	172	650	2.0"
V1200	88010613	V1200 Φ 48" Top Mount Filter, 2.0" valve Vseries Sand Filter	227	860	2.0"



V Series Filter is equipped with :

1. 6-way clamp/bolt style multiport valve (1.5"MPV01, 2"MPV02, 2.5"MPV12)
2. universal standard of union connection
3. pressure gauge
4. lateral system

PREMIUM SWIMMING POOL HEATERS



QUALITY GUARANTEED



HAYWARD CSPA XI 11 ELECTRIC SPA HEATER 11KW

Hayward electric spa heaters contain all of the sophisticated features and capabilities of heaters twice their size. The electric heaters fit into compact spaces - even under spa skirts or steps. Like all Hayward heaters, they are easy to install and service.

Model	KW	Port Size	Volts
CSPAXI11	11.0	1.5"	230



HAYWARD UNIVERSAL H-SERIES GAS POOL HEATER

Universal H-Series Low NOx heater has an industry-leading thermal efficiency and complies with all current California air quality emission standards. The low NOx emission makes it a perfect choice for the environmentally concerned pool owner.

GAS HEATER	BTU	Port Size	Volts
H150FDP	150,000	2"	230
H250FDP	250,000	2"	230
H400FDP	400,000	2"	230
H500FDP	500,000	2"	230



HAYWARD HEAT PRO SERIES HEAT PUMP

HeatPro® heat pumps provide longer-lasting performance.

HEAT PUMP			
HP21124T	110,000	2"	230
HP21254T	125,000	2"	230
HP21404T	140,000	2"	230
HP31204T	Heat / Cool	2"	230

PREMIUM SWIMMING POOL HEATERS



QUALITY GUARANTEED



COATES USA 11KW ELECTRIC INLINE SPA HEATER

The built-in flow switch prevents operation when there is no water flow and allows operation at flow rates between 15GPM and 80GPM. The stainless steel tank is designed to optimize heat transfer by directing the waterflow over the incoloy elements efficiently.

MODEL NUMBER	KW	VOLTAGE	PHASE	AMPS	BTU'S P/H	SHIPPING WT.
12411ST	11.0	240	1	46	37,543	19 lbs.



MASTER TEMP GAS HEATER

Features strong corrosion resistant stainless steel burners, durable headers, a composite top, and a weather-proof anodized aluminium exterior. It also features energy - saving "Hot Surface" ignition, fast heat-up, and exceptional efficiency for lower cost.

250 - PN: 460733; 250,000 BTU Heating capacity

300 - PN: 460735; 300,000 BTU Heating capacity

400 - PN: 460737; 400,000 BTU Heating capacity



ULTRATEMP HEAT PUMPS

Features digital controls with dual thermostats offer precise temperature control to maintain the desired separate water temperature in pool/spa combinations without overheating or wasting energy. With self-diagnostic control panel monitors and troubleshoots heat pump operations to ensure safe, dependable operation.

110 - PN: 460932; 108,000 BTU Heating capacity; 5.8 COP

120 - PN: 460933; 125,000 BTU Heating capacity; 5.5 COP

140 - PN: 460935; 140,000 BTU Heating capacity; 5.8 COP



PREMIUM SPA BLOWERS



QUALITY GUARANTEED



HAYWARD SPA AIR BLOWER

PEACE AND QUIET JUST GOT A MAJOR UPGRADE. Featuring an innovative, durable design, our new Spa Blower delivers quiet performance and powerful, soothing bubbles that instantly enhance any spa experience. A unique motor with replaceable parts extends product life, while a 1-year warranty offers added peace of mind. Plus, with simple installation and maintenance, our Spa Blower provides maximum relaxation season after season.

Model	HP	Volts
SPB102	1.0	230
SPB152	1.5	230
SPB202	2.0	230



SILENCER SPA AIR BLOWER

The new Silencer By Air Supply has taken a quantum leap in quiet performance. The unique motor mount is the secret to our success. A thick rubber cup encases the fan while allowing the motor to vibrate freely on a flexible rubber base. This combination eliminates noise so well that virtually no foam is required. Many competitive blowers use filter foam to reduce noise, but foam may clog over time causing starvation and overheating.

Model	HP	Volts
SPB102	1.0	230
SPB152	1.5	230
SPB202	2.0	230

BLOWER VS WATER JET SIZING

BLOWER SIZE	VOLTS	AMPS	NUMBER OF WATER JETS
1 HP	120/240	6.7/3.5	4 TO 8
1.5 HP	120/240	8.0/4.0	8 TO 12
2.0 HP	120/240	10.0/6.0	14 OR MORE

PREMIUM ROBOTIC POOL CLEANERS

maytronics
Exceptional Pool Experience



QUALITY GUARANTEED



DOLPHIN AUTOMATIC POOL CLEANERS

Dolphin robotic pool cleaners deliver automated, high-performance pool cleaning efficiently and effectively. Dolphin have consistently been at the forefront of innovation. With decades of expertise in automatic pool cleaners, every Dolphin combines advanced technologies with proven reliability so you can enjoy a constantly clean pool with little effort.

Effortless operation

- Top-access filtration system – easy to remove and clean
- Lightweight easy to handle and store
- Fast, debris-free water release – easy to remove from pool

Crystal-clear cleaning results

- Active brushing action, scrub away dirt and debris
- Effective, easy-to-use fine filtration system
- Efficient dirt collection – Collects fine and rough debris

Peace of mind

- Proven reliability – made by Maytronics, the leader in robotic pool cleaners
- Certified ISO9001 quality standard



S SERIES

	S50	S100	S300i
Ideal Pool Length	8 m	10 m	12 m
Cleaning Coverage	Floor	Floor and Walls	Floor, Walls, Waterline
Cleaning Cycle	1.5 hours	2 hours	1.5 / 2 / 2.5 hours
Weekly Timer	No	Yes	Yes
Smartphone Dolphin App Control	No	No	Yes - program set-up, operational control & manual navigation
Operation Delay	No	No	Yes
Filtration	Easy-Clean net canister	Easy-Clean net basket	Easy-clean net & choice of ultra-fine filters
Cable Length	12 m	15 m	18 m
Weight	6.3 kg	6.5 kg	7.5 kg
Swivel Software	Yes	Yes	Yes
Warranty	24 months (limited)	24 months	24 months



PREMIUM ROBOTIC POOL CLEANERS



QUALITY GUARANTEED



DOLPHIN AUTOMATIC POOL CLEANERS

Pool Cleaning Made Easy

All swim, no work? Sounds perfect! Let the smart featured M400 and M500 make your pool shine. With an impressive range of benefits and features, it is no wonder these cleaners are in high demand.

Effortless operation

- Top-access filtration system – easy to remove and clean
- Lightweight easy to handle and store
- Fast, debris-free water release – easy to remove from pool

Crystal-clear cleaning results

- Active brushing action, scrub away dirt and debris
- Effective, easy-to-use fine filtration system
- Efficient dirt collection - Collects fine and rough debris

Peace of mind

- Proven reliability – made by Maytronics, the leader in robotic pool cleaners
- Certified ISO9001 quality standard



M SERIES

	M400	M500
Ideal Pool Length	up to 12m	up to 12m - 15m
Cycle Time	2.5 hours	1.5 / 2.5 / 3.5 hours
Pool Coverage	Floor, Walls and Waterline	Floor, Walls and Waterline
Filtration	Fine & Ultra-fine Filter Cartridge	Fine & Ultra-fine Filter Cartridge
Brushing	Active brush spins at 2x the speed of the robot, resulting in enhanced all-surface cleaning	Active brush spins at 2x the speed of the robot, resulting in enhanced all-surface cleaning
Wall Climbing	yes	yes
Cable Length	18m	18m
Weight	10.5kg	10.5kg
Warranty (limited)	36 months	36 months



PREMIUM ROBOTIC POOL CLEANERS



Three smart robots with a one-track mind for clean.



QUALITY GUARANTEED



**Two cleaning speeds:
fast and really fast.**

- Able to scour pool floor, covers, walls and waterline in 3 hours.
- TigerShark QC can perform a quick 90-minute cleaning cycle.
- TigerShark Plus has a wireless handheld remote that can be used to steer the cleaner into hard-to-reach areas.



Specifications	TigerShark	TigerShark Plus	TigerShark QC
Part Number	RC9950CUB	RC9955CUB	RC9990CUB
Remote Control	No	Yes	No
Pool Coverage	Pool floor, walls, covers, waterline	Pool floor, walls, covers, waterline	Pool floor, walls, covers, waterline
Cleaning Cycle	3 hours	3 hours	3 hours / 90 minutes Quick Clean
Pool Size	Up to 20' x 40'	Up to 20' x 40'	Up to 20' x 40'
Pool Surface	Gunite, Vinyl, Fiberglass, Pebble and Tile*	Gunite, Vinyl, Fiberglass, Pebble and Tile*	Gunite, Vinyl, Fiberglass, Pebble and Tile*
Cord Length	55'	55'	55'
Power Supply Input Voltage	115 VAC 60 Hz	115 VAC 60 Hz	115 VAC 60 Hz
Power Supply Output Voltage	24 V DC	24 V DC	24 V DC
Weight	21.5 lbs	21.5 lbs	21.5 lbs
Warranty	1 year	3 year	3 year

One-of-a-kind powerfully efficient vacuum strength.

- Able to scour pool floor, covers, walls and waterline in 3 hours.
- TigerShark QC can perform a quick 90-minute cleaning cycle.
- TigerShark Plus has a wireless handheld remote that can be used to steer the cleaner into hard-to-reach areas.

Zero hassle for simple and painless maintenance.

- Unique cartridge filter system makes emptying easy, just open the cleaner, remove the cartridge and rinse with a hose.
- Reinforced cartridge elements ensure TigerShark filters last longer and cost less to maintain.
- No extra hoses, hookups or pumps required



POOL FITTINGS

WHITE GOODS



QUALITY GUARANTEED



Outlet Fittings - Surface Skimmer

Outlet Fittings - Heavy Duty Skimmer

Outlet Fittings - Standard Skimmer

Outlet Fittings - VGB Anti Vortex Main Drain

Outlet Fittings - Main Drain

Outlet Fittings - Suction Fitting and Vacuum Fitting

Inlet Fittings - Return Inlet

Inlet Fittings - Wall Return and Floor Inlet

Inlet Fittings - SPA Jet

Inlet Fittings - Eyeball Jet and Jet Body

Grating System - TPV Antiskid Grating

Grating System - Grating and Floor Pad

<p>Vacuum Fitting/ Receptacle For Concrete Pools</p> <p>SP-1022 1 1/2" PVE White SP-1022S 1 1/2" Socket White</p>	<p>Directional Flow Inlet Fittings</p> <p>SP-1419B hydrostream 1/2" opening SP-1419C hydrostream 1/2" opening SP-1419D hydrostream 1/2" opening SP-1419E hydrostream 1" opening</p>	<p>All-Purpose Plug</p> <p>SP-1022-C 1 1/2" All-Purpose Plug, White, with O-Ring</p>	<p>Push Plug</p> <p>SP-1022-B 1 3/8" Plug, White, with gasket</p>
<p>Extended Flange Directional Flow, Eyeball Fitting</p> <p>SP-1411D 1 1/2" MP Hydrostream 1/2" opening SP-1422D 1 1/2" MP Hydrostream Insider 1/2" opening SP-1422E 1 1/2" MP Hydrostream Insider 1" opening Type 1422D 2" Hydrostream Insider Fitting for 2" Schedule 40 PVC pipe</p>	<p>Gutter Drain Attractive and Streamlined</p> <p>Model No. SP-1019 Description: 2" PIP plus 2" Socket Connection, White Body and Grate.</p>	<p>Wall Inlets Adjustable and Non-Adjustable</p> <p>White Body and Grate. SP-1424 Illustrated.</p>	





POOL

LIGHTS & ACCESSORIES



QUALITY GUARANTEED




Specifications - AstroLite™

Thermoplastic Face Rim Model	Stainless Steel Face Rim Model	Description
SP0580	SP0580S	100 watt, 12 volt light — 15', 30', 50', 75' or 100' cord
SP0581	SP0581S	300 watt, 12 volt light — 15', 30', 50', 75' or 100' cord
SP0582L	SP0582SL	300 watt, 120 volt light — 15', 30', 50', 75' or 100' cord
—	SP0584SL	400 watt, 120 volt light — 30', 50', 75' or 100' cord
SP0583L	SP0583SL	500 watt, 120 volt light — 15', 30', 50', 75' or 100' cord

Models with suffix "L" are equipped with Automatic Thermal Switch (ATS)

ASTROLITE

Model	Wattage	Volts		Cord Ft.
SP0590SL15	100	12	Small	15
SP0590SL30	100	12	Small	30
SP0590SL50	100	12	Small	50
SP0581S15	300	12	Big	15



Universal ColorLogic LED pool and spa lights retrofit virtually any existing pool or spa while delivering best-in-class performance and illumination for truly vivid color.

COLOR LOGIC

Model	Wattage	Volts		Cord Ft.
LSCUS11030	25	12	Small	30
LPCUS11030	50	12	Big	30

HAYWARD IM LIGHTS



Model	Wattage	Volts		Cord Ft.
IM3640 Halogen	100	12		12
IM3680 White	18	12		12
IM3680 RGB	18	12		12
IM5880 White	18	12		12
IM5880 RGB	18	12		12

CRYSTAL LOGIC



Model	Wattage	Volts		Cord Ft.
LSLUS11030	25	12	Small	30
LPLUS11030	50	12	Big	30

POOLPRO CHINA



Model	Wattage	Volts		Cord Ft.
RGB BIG	18	12		10
Warm White Big	18	12		10
RGB Small	8	12		10
Warm White Small	8	12		10
PoolPro Deck Box				
PoolPro Deck Box Cover w/ gasket (Also Fits Hayward)				

COLORLOGIC LAMINARS				
Model	Wattage	Volts		Cord Ft.
WFL100	25	12		30
Colologic 320	25	12		30
Deck Jet 500			LACUSS11030	
Colologic Bubbler				
Sheer Falls 2Ft			Hayward	
Sheer Falls 3Ft			Hayward	
Sheer Falls 4Ft			Hayward	





POOL LIGHTS & ACCESSORIES

POOL

LED LIGHT TRANSFORMERS



QUALITY GUARANTEED



HAYWARD PRO TRANSFORMER TRM300

low voltage transformers are designed to provide safe 12 volt electrical supply to underwater lights and low voltage fixtures of all types.

TRM300	300 watts	12 - 14V
--------	-----------	----------



POOLPRO TRANSFORMER CHINA

	100 watts	12V
	150 watts	12V
	250 watts	12V
	300 watts	12V
	350 watts	12V



JIMSON TRANSFORMER PHILIPPINES

100% original JIMSON Dry-Type Voltage Transformer 30/75/150 Watts

Used for Voltage Transformer for Underwater Pool Light 12 Volt

Rating: 30 / 75 / 150 / 350 Watts

Voltage Input: 220 - 240 Volt

Voltage Output: 12/14 Volt

Cycles: 50/60 Hz




POOLMASTER
— BUILT TO LAST —

POOL CLEANING MATERIALS



QUALITY GUARANTEED



POOL ACCESSORIES



CONTACT US
02 8-557-1585



Clients

Our portfolio includes a wide range of projects that span across various industries, ranging from hospitality and leisure to healthcare and education. Poolmaster's team of experts work closely with each client to understand their unique needs and preferences, and then create a custom solution to meet those requirements.

- **HOTEL**


As a hotel client, you want to ensure that your guests have the best possible experience during their stay, and that includes enjoying your pool facilities.

- **RESORT**

If you are a resort owner or manager looking for high-quality pool products, Poolmaster has got you covered. Our products are designed to provide your guests with a safe and enjoyable pool experience.

- **RESIDENTIAL**

Swimming pools are an integral part of residential properties, especially condominiums and houses. However, maintaining a swimming pool can be a challenging task. This is where Poolmaster products come in handy.



- **WATER TREATMENT**

At Poolmaster, we understand the importance of clean and safe water for your facility. That's why our products are designed to provide the best possible results when it comes to water treatment and maintenance.

- **HEALTHCARE**

Disinfection is a critical aspect of maintaining a healthy and safe environment in hospitals and healthcare facilities.

Our disinfectants are safe, effective, and easy to use, making them an ideal choice for busy healthcare professionals.

CLIENT PORTFOLIO



www.poolmaster.com.ph



02 8-557-1585



19B Caimito St., cor. MRT Ave., Central Signal Village, Taguig City, Philippines, 1633

POOL TIPS & TRICKS!

SUPPLY | DESIGN & BUILD | REPAIR

POOLMASTER
—BUILT TO LAST—

POOL CHLORINE APPLICATION

Directions:

For new or newly-refilled pools, add 10 oz. of chlorine per 10,000 gallons of pool water. Then run the filtration system for 24 hours. Adjust ph to 7.4 - 7.6 and test for chlorine residual. Do not allow bathers to swim when chlorine residual is above 2.00 PPM. Then simply follow the chlorine dosage shown below.

Superchlorination: Should pool water appear cloudy or dirty, add 20 oz. of chlorine concentrate per 10,000 gallons, allowing the pool filter to run so as to turn the pool water over in the pool. This process should be repeated until the pool water is clear and sparkling. Normal chlorination is not necessary during this process. Do not allow bathers when chlorine residual is over 2.00 PPM.



Calcium Hypochlorite 70% Granular

Pool Capacity (US Gal)	Daily Dosage	
	Unstabilized Pool Water	Stabilized Pool Water
5000	1/8 kg	1/16 kg
10000	1/6 kg	1/12 kg
15000	1/4 kg	1/8 kg
20000	2/5 kg	1/5 kg
25000	1/2 kg	1/4 kg
50000	1 kg	1/2 kg

IN NEED OF POOL EXPERTS?



www.poolmaster.com.ph



02 8-557-1585

+63 915 -888 -1660



19B Caimito St., cor. MRT Ave., Central Signal Village, Taguig City, Philippines, 1633

POOL TIPS & TRICKS!

SUPPLY | DESIGN & BUILD | REPAIR

POOLMASTER
BUILT TO LAST

✓ SAFER & EASIER TO USE THAN
MURIATIC ACID

✓ LOWERS PH LEVEL OF
SWIMMING POOL & SPA

DRY ACID APPLICATION

How much Dry Acid do I need to put?

Dose 100 grams of Dry Acid for 10 cubic meter / 2,700 gallons of pool water.

Dose 1 KG of Dry Acid for 50 cubic meter / 13,200 gallons of pool water.

Application:

Approx. 10 gram dry acid for 1,000 liters pool water to lower 0.5pH.

**Do not add more than 1 KG Dry Acid for each 10,000 gallons as it may cause the pool to become acidic.*

**Never add dry acid more than 3 times per day.*



Sodium Bisulphate / Natrium Bisulfat

Directions:

1. Pre-dissolve the dry acid first by adding the dry acid into a large plastic bucket of water
2. Pour the acid solution into the deep end of the pool, away from the skimmer and the fixtures.
3. The Acid should be added when the pump is on and running.
4. Retest the pH of the water in 4 hours and add more acid if needed.

IDEAL PH LEVEL : 7.2 -7.6

IN NEED OF POOL EXPERTS?



www.poolmaster.com.ph



02 8-557-1585

+63 915 -888 -1660





19B Caimito St., cor. MRT Ave., Central Signal Village, Taguig City, Philippines, 1633

COMMON POOL DESIGNS


• RIM FLOW

Rim flow spas—also called mirror spas, full-perimeter spas, and 360-degree overflow spas—represent a dramatic style of elevated custom spa with specially configured exposed tile- or stone-covered walls that allow the water inside to sleekly run over the spa's entire perimeter into the swimming pool below.





• SKIMMER


The term “skimmer pool” comes from a device called skimmer. This unit takes water from the reservoir for cleaning and disinfection. The skimmer can be found under the top edge of the swimming pool.



IN NEED OF POOL EXPERTS?

 www.poolmaster.com.ph


 02 8-557-1585
 +63 915 -888 -1660

 19B Caimito St., cor. MRT Ave., Central Signal Village, Taguig City, Philippines ,1633

COMMON POOL DESIGNS


• INFINITY

A swimming pool in which the top of the water is at the same level as the edges surrounding the pool, and seems, to someone in the pool, to stretch to the horizon.





• OLYMPIC / TRAINING


An Olympic swimming pool is one that is designed to hold competitions such as those held at the Olympic Games. According to the International Swimming Federation an Olympic pool will always be 50 meters.



IN NEED OF POOL EXPERTS?

 www.poolmaster.com.ph

 02 8-557-1585
 +63 915 -888 -1660

 19B Caimito St., cor. MRT Ave., Central Signal Village, Taguig City, Philippines ,1633


COMMON POOL DESIGNS

• ROCKWORKS

A swimming pool design that is associated with geological features to mimic the design found in nature.





BASIC SWIMMING POOL PLUMBING DESIGN




1. Skimmer
2. Main drain
3. Inlet
4. JetSwim
5. Light
6. Pump
7. Filter
8. Electric heater
9. Check valve
10. Drain

IN NEED OF POOL EXPERTS?

 www.poolmaster.com.ph


 02 8-557-1585
 +63 915 -888 -1660

 19B Caimito St., cor. MRT Ave., Central Signal Village, Taguig City, Philippines ,1633

POOLMASTER
BUILT TO LAST

**NEED EXPERT HELP WITH YOUR SWIMMING POOL
NEEDS?**

GET IN TOUCH

 19B Caimito St., cor. MRT Ave., Central Signal Village, Taguig City, Philippines ,1633



02 8-557-1585 | +639158881660



theofficialpoolmaster88@gmail.com



www.poolmaster.com.ph



PoolMaster



POOLMASTER



PoolMaster



officialpoolmaster

Crafting Excellence, Built to Last